



Micropiles typical details
(Scale: 1 : 20)

MATERIAL SPECIFICATION			
MATERIAL	ELEMENT	TYPE	MATERIAL COEFFICIENTS
Micropiles	Tubular CHS Reinforcement	F_{yk}=550 MPa	γ_S=1,1
	Grout	F_{ck}=25 MPa	γ_C=1,5

(*) CONCRETE TYPE TO BE SPECIFIED BY THE DESIGN TEAM, ACCORDING TO GROUND AGGRESSIVITY AND CONCRETE DESIGN CODE.

CEMENT TYPE AND GROUT MIX				
ELEMENT	CEMENT TYPE	COVER	WATER/CEMENT RATIO	MINIMUM CEMENT CONTENT
MICROPILES (GROUT)	CEM I 42,5 N	≥ 2,5 cm	0,45 - 0,55	-

NOTES:

- WELDING OF CONNECTION REINFORCEMENT TO TUBULAR CHS IN ACCORDANCE WITH UNE EN ISO 17660-12008 STRUCTURAL WELDING
- WELD LENGTH L >= 4d, MIN. SEPARATION 2d BETWEEN WELDS
- WELD THROAT WIDTH >= 0,3d
- MIN. YIELD STRENGTH OF WELD MATERIAL 550 MPa

MICROPILE	DIA (mm)	CHS TUBULAR REINFORCEMENT
TYPE	200	127x9mm

PILE LOCATION	CHS STEEL GRADE	CONNECTION REINFORCEMENT	No. OF WELDS	ESTIMATED MICROPILE LENGTH
RETAINING WALL	F_{yk}=550MPa	7B16L	4	8,00m.
PILECAPS	F_{yk}=550MPa	7B16L	4	21,00m.

Rev.	Date	Description	Drawn by	Check by

NOSA Ltd.
Suite 9.1, 9th Floor, ICC
2A Main Street
Gibraltar, GX11 1AA
t: +350 20075000
m: +350 58008085 / +35057056000
e: info@nosa.gi

Client: Client X

Project Title: 1st Rock Street

Drawing Description: Substructure details - Micro piles

Drawing status: Project Status

Scale:	Size:	Date:	Drawn by:	Revision:
As shown	ISO A1	10/08/24	Author	

Drawing Number:

Project Number		Originator		Functional Breakdown		Spatial Breakdown		Form Identifier		Discipline		Number
12345	-	NOSA	-	ZZ	-	ZZZ	-	D	-	S	-	4001