





Micropiles typical details
(Scale: 1 : 20)

| MATERIAL SPECIFICATION | | | |
|---|---|---|---|
| MATERIAL | ELEMENT | TYPE | MATERIAL COEFFICIENTS |
| Micropiles | Tubular CHS Reinforcement | $F_{yk}$=550 MPa | $\gamma_S$=1,1 |
| | Grout | $F_{ck}$=25 MPa | $\gamma_C$=1,5 |

(*) CONCRETE TYPE TO BE SPECIFIED BY THE DESIGN TEAM, ACCORDING TO GROUND AGGRESSIVITY AND CONCRETE DESIGN CODE.

| CEMENT TYPE AND GROUT MIX | | | | |
|---|---|---|---|---|
| ELEMENT | CEMENT TYPE | COVER | WATER/CEMENT RATIO | MINIMUM CEMENT CONTENT |
| MICROPILES (GROUT) | CEM I 42,5 N | ≥ 2,5 cm | 0,45 - 0,55 | - |

NOTES:

- WELDING OF CONNECTION REINFORCEMENT TO TUBULAR CHS IN ACCORDANCE WITH UNE EN ISO 17660-12008 STRUCTURAL WELDING
- WELD LENGTH L >= 4d, MIN. SEPARATION 2d BETWEEN WELDS
- WELD THROAT WIDTH >= 0,3d
- MIN. YIELD STRENGTH OF WELD MATERIAL 550 MPa

| MICROPILE | DIA (mm) | CHS TUBULAR REINFORCEMENT |
|---|---|---|
| TYPE | 200 | 127x9mm |

| PILE LOCATION | CHS STEEL GRADE | CONNECTION REINFORCEMENT | No. OF WELDS | ESTIMATED MICROPILE LENGTH |
|---|---|---|---|---|
| RETAINING WALL | $F_{yk}$=550MPa | 7B16L | 4 | 8,00m. |
| PILECAPS | $F_{yk}$=550MPa | 7B16L | 4 | 21,00m. |

| Rev. | Date | Description | Drawn by | Check by |
|---|---|---|---|---|

**NOSA Ltd.**
Suite 9.1, 9th Floor, ICC
2A Main Street
Gibraltar, GX11 1AA
t: +350 20075000
m: +350 58008085 / +35057056000
e: info@nosa.gi

Client: Client X

Project Title: 1st Rock Street

Drawing Description: Substructure details - Micro piles

Drawing status: Project Status

| Scale: | Size: | Date: | Drawn by: | Revision: |
|---|---|---|---|---|
| As shown | ISO A1 | 10/08/24 | Author | |

Drawing Number:

| Project Number | | Originator | | Functional Breakdown | | Spatial Breakdown | | Form Identifier | | Discipline | | Number |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 12345 | - | NOSA | - | ZZ | - | ZZZ | - | D | - | S | - | 4001 |